

Subject : Step by step to update firmware in EPM-1525 for specific panel supporting		
Document No: S12012	Date: 2012/07/24	
Model Name. EPM-1525	AE :	
Purpose :		
This document shows you how to setup/program firmware for Realtek RTD2553V chipset		

# Before you update firmware, please make sure you have correct firmware for your panel.

Contact Avalue to get necessary AP, firmware and tool.

# Step by Step to update firmware :

# equipments:

- 1, ISP Board (P/N:E9697152502R)
- 2, Pin-to-Pin 25-pin parallel cable (Female to Male)
- 3, DB15 VGA cable (Male to Male)



- 1, A PC with XP professional
- 2, Realtek firmware update tools : RealtekToolsetup.exe
- 3, Port I/O driver : Port95nt.exe
- 4, firmware: contact Avalue (firmware supports AU M150XN07 by default)

# Prepare environment:

1, Connect ISP Board (E9697152502R) to your PC LPT port.

### Avalue Technology Inc.


www.avalue.com.tw sales@avalue.com.tw Tel:+886-2-82262345 Fax:+886-2-82262777

www.avalue.co


Avalue China sales.china@avalue.com.cn Tel: +86-21-5426-3399 Fax: +86-21-6495-0370







2, Connect ISP Board (E9697152502R) to EPM-1525 DB15 connector



## 3, offer power to EPM-1525

## Program procedure:

1, install "RealtekToolsetup.exe" and "Port95nt.exe" in your PC with WinXP.

There will be a shortcut named "RTDTool\_VER3.0" (2010) on the desktop.

- 2, execute "RTDTool\_VER3.0" by double click
- 3, Click "RTD 2120 ISP"

### Avalue Technology Inc.



www.avalue.co


Avalue China sales.china@avalue.com.cn Tel: +86-21-5426-3399 Fax: +86-21-6495-0370



Configuration	_ 🗆 🗙	
Select RTD	Communication	
• RTD2523	IC	
	C RS232	
C RTD2323	Select Com Port	
C RTD2363	Com 1	
	Select Baud Rate	
C RTD2023S	9600	

4, Click the <64K> button to select the firmware file "RTDScalarSeries.hex" (contact Avalue for correct firmware) Click the <64~96> button to select "RTDScalarExtend.hex" (contact Avalue for correct firmware) Select "Both" and "AUTO" item.

Click *button to flash the firmware into EPM-1525.* 





- 5, After flash the firmware, please make sure there is no CRC error in the MsgBox.
  - Then remove power cord for EPM-1525

REALTEK ISP VER 3.0		
C:\Documents and Settings\wilsonh\桌面\PNV_Ver_009_20101  C:\Documents and Settings\wilsonh\桌面\PNV_Ver_009_20101		
Erase MCU OK. Program BANK 1 100 % Calculate CRC 0x5F Read CRC 0x5F CRC OK. Program BANK 2 100 % Calculate CRC 0xF4 Read CRC 0xF4	<ul> <li>Main</li> <li>Second</li> </ul>	<ul> <li>AUTO</li> <li>C Frase</li> </ul>
CRC OK.	<ul> <li>e Both</li> <li>e 1 To 4 Writer</li> </ul>	

#### Avalue Technology Inc.

www.avalue.com.tw sales@avalue.com.tw Tel:+886-2-82262345 Fax:+886-2-82262777

7F, 228, Lian-Cheng Road, Chung Ho City, Taipei, Taiwan R.O.C. BCM Advanced Research BCMSales@bcmcom.com Tel: +1-949-470-1888 Fax: +1-949-470-0971

Avalue China sales.china@avalue.com.cn Tel: +86-21-5426-3399 Fax: +86-21-6495-0370

# www.avalue.co